UTT/0215/12/FUL - STANSTED

PROPOSAL: Demolition of existing buildings and erection of 14 No.

dwellings, retail and office unit, including associated garages,

car parking and landscaping

LOCATION: Land to r/o of 14 Cambridge Road Stansted

APPLICANT: Bellway Homes Ltd

AGENT: Strutt and Parker LLP

GRID REFERENCE: TL 511-251

EXPIRY DATE: 10.05.2012

CASE OFFICER: Maria Tourvas

APPLICATION TYPE: Major

1. NOTATION

1.1 Within Development Limits, Part protected Retail Frontage/Town Centre Policy SM1, adjacent to Grade II listed buildings

2. DESCRIPTION OF SITE

- 2.1 The site is predominantly set back off Cambridge Road to the rear of properties no. 12-30 (even). This comprises a single storey shop located to the front of the site on Cambridge Road (no.14), and to the rear/centre of the application site there are a number of two-storey and single storey units (total of 8 units). These units break down as the following:
 - Building 1: Unit is recently used by Lan One Computers (computer repair shop);
 - Building 2: Until recently used by Vaio Pak Packaging Company:
 - Building3: Currently vacant but has been used by You're Furnished in the past;
 - Building 4: Currently vacant but has been used by You're Furnished in the past;
 - Building 5: Currently vacant but has been used by You're Furnished in the past;
 - Building 6: Currently vacant but has been used by Express Framing in the past;
 - Building 7 & 8: Used by You're Furnished
- 2.2 The site covers a total area of 0.42 hectares.
- 2.3 The site was previously used by Sworders Fine Art Auctions. However, the site is owned and run by You're Furnished and there are 2 sub-tenants (Lan One and Expressive Design) which have short/expired leases. There is a standalone building which is located adjacent to the shared boundary with 22 Cambridge Road has been previously been refurbished in 1997 (building 2). The buildings on site are

predominantly dated, in a poor state of repair and require work. The application site to the north adjacent to the rear of properties fronting Clarence Road, appears to be a secluded area. This is used more as 'waste ground' rather than parking area.

- 2.4 There is a 1.5m high close boarded fence to the rear of the site adjacent to the Crafton Green Car Park. There are high level conifers along the shared eastern boundary. There are also close boarded fences along the northwest, north and northeast, with slightly lower fencing along the northeast boundary, which relate to two-storey houses fronting Clarence Road.
- 2.5 Fronting Cambridge, other than the single storey shop as discussed above, there is a Tesco's store, a back clinic and Co-operative food store that back onto the application site. There is also a row of semi detached single family dwellings. Half of this row of houses are Grade II Listed.
- 2.6 To the south of the application is the Crafton Green Car Park also consists of the local clinic and library.
- 2.7 The site's access is taken from Cambridge Road.

3. DESCRIPTION OF PROPOSAL

- 3.1 The application is for the demolition of 8no. existing employment buildings and the erection of 14no. residential dwellings. This will be a mixture of detached and semi detached two-storey properties with associated garage provision. The scheme also involves the erection of a new retail unit with office space over, which would be two-storeys fronting Cambridge Road.
- 3.2 There would also be associated car parking for both the residential and commercial unit and landscaping.
- 3.3 The dwellings are proposed to be 6 x 3 bedroom units, 4x 4 bedroom units and 4 x 5 bedroom units. Plot 6 is proposed to be a designated wheelchair unit, capable of being wheel chair adaptable.
- 3.4 A 5 bar timber gate is proposed along the front access of the site, setback from the main road.

4. APPLICANT'S CASE

4.1 The following documents have been submitted with the application:

Design and Access Statement - undated

Planning Statement - January 2012

Transport Statement – January 2012

Report on Impact of Existing Commercial Buildings on Plots 1 and 2 – January 2012

Site Marketing Assessment Report – January 2012

Geotechnical and Geo-environmental Report - March 2011

Flood Risk Assessment – January 2012

Utilities Statement - January 2012

Energy Statement - January 2012

Statement of Community Engagement – 27 January 2012

Site Waste Management Plan – 9 January 2012

4.2 Consultation and Community Involvement

As part of the application process a public exhibition has been undertaken by the applicant prior to the submission of the application in accordance with the Council's Statement of Community Involvement.

The initial application was part of two briefing letters to residents, two sets of meetings with residents and door to door surveys have been carried out. It has been offered that the applicant would meets with residents at their own homes at times of the day convenient to them, telephone contact and discussion have been held with residents as well as a one day public exhibition which involved local groups, parish councils etc.

A Statement of Public Consultation has been submitted as part of the application.

5. RELEVANT HISTORY

- 5.1 UTT/111/75 Erection of warehouse, packing case store and garage Refused July 1975
- 5.2 UTT/206/76 Linked corridor, showroom warehouse to existing showrooms Granted April 1976
- 5.3 UTT/453/76 Erection of warehouse and garage Granted July 1976
- 5.4 UTT/1446/95 Change of use from Class A1 to auction rooms Granted April 1996

6. POLICIES

6.1 National Policies

National Planning Policy Framework

6.2 East of England Plan 2006

Policy SS1 - Achieving Sustainable Development

Policy SS2 - Overall Spatial Strategy

Policy SS4 - Towns Other than Key Centres and Rural Areas

Policy E1 – Job Growth

Policy E2 – Provision of Land for Employment

Policy E3 – Strategic Employment Sites

Policy E5 - Regional Structure of Town Centres

Policy T1 – Regional Transport Strategy Objectives and Outcomes

Policy T2 - Changing Travel Behaviour

Policy T3 - Managing Traffic Demand-

Policy T4 - Urban Transport

Policy T7 - Transport within Rural Areas

Policy T8 – Local Roads

Policy T13 - Public transport accessibility

Policy ENV1 - Green Infrastructure

Policy ENV3 - Biodiversity and Earth Heritage

Policy ENV7 - Quality in the Built Environment

Policy ENG1 - Carbon Dioxide Emissions and Energy Performance

Policy WAT4 - Flood Risk Management

6.3 Essex Replacement Structure Plan 2001

No policies relevant.

6.4 Uttlesford District Local Plan 2005

Policy S1 – Development Limits for the Main Urban Areas

Policy SM1 - Local Centres

Policy E1 - Distribution of Employment Land

Policy E2 – Safeguarding Employment Land

Policy RS1 - Access to Retailing and Services

Policy RS2- Town and Local Centres

Policy GEN1 - Access

Policy GEN2 – Design

Policy GEN3 - Flood Protection

Policy GEN4 – Good Neighbourliness

Policy GEN6 - Infrastructure Provision to Support Development

Policy GEN7 - Nature Conservation

Policy GEN8 – Vehicle Parking Standards

Policy ENV2 - Development Affecting Listed Buildings

Policy ENV3 - Open Spaces and Trees

Policy ENV12 - Protection of Water Resources

Policy ENV14 - Contaminated Land

Policy ENV15- Renewable Energy

Policy H1 - Housing Development

Policy H3 - New Houses within Development Limits

Policy H4 - Backland Development

Policy H10 - Housing Mix

6.5 Stansted Mountfitchet Community Plan (2011)

The Plan states over the years the number of shops have reduced in the Parish and that they have done well to hold as many retailers as they have. The Plan discusses the widespread fear of crime whether actual or perceived, even though the reality is less and the need for more Police Officers on the streets which would reduce the perception and the need for better street lighting.

The Village Plan discusses issues relating to roads traffic and parking in the area, whereby Cambridge Road is highlighted as a danger both to pedestrians and drivers.

It is highlighted within the Plan the need for more smaller family dwellings (2 and 3 bedroom units) and the need for affordable housing.

The document identified that Stansted has enlarged over the years and states that any further attempts to significantly enlarge Stansted would be resisted. The Plan identifies that the Uttlesford District Council's Strategic Housing and Land Availability Assessment (SHLAA) identifies a number of site that could potentially bring forward housing scheme s one of those sites identified is the subject application site and it is stated that the Parish Council agrees with this site (page 13 of Community Plan).

It is discussed within the document the local publics likes and dislikes about living in the Parish. The dislikes included amongst other things traffic and anti-social behaviour.

7. CONSULTATIONS

- 7.1 <u>Planning Policy:</u> verbally reported: The site is not allocated for any particular use. It is within the development limits where there is a policy presumption in favour of appropriate development.
- 7.2 Policy E2 states that the development of employment land for other uses outside the key employment areas will be permitted if the employment use has been abandoned or the present use harms the character or amenities of the surrounding area.
- 7.3 The site is surrounded on three sides by residential properties and there is potential for noise and disturbance is not necessarily compatible with these uses but some other employment use could take place on the site without undue disturbance and as there is limited employment land within the village as previously advised evidence of marketing for employment use would need to be submitted in support of the application in order to demonstrate that there is no demand for employment use of the site.
- 7.4 In order for this application to be approved the Council has to be satisfied that:
 - a) there is no demand for this site for business use or
 - b) that the use proposed will generate local jobs
- 7.5 <u>Access Officer:</u> Plots 8 & 9 (entrance level WC this requires access through the kitchen and into a further 'lobby' area. This would not be very suitable for a wheelchair user, either as a resident or a visitor. This arrangement could be improved.
- 7.6 There are 14 dwellings which will trigger the requirement for a wheelchair accessible unit under the SPD with an internal layout that meets this need with parking and require a plot to be specified.
- 7.7 The retail unit shows a stepped access and would need to be DDA compliant.
- 7.8 Following amendments further comments submitted: Plot 6 is wheelchair accessible. Drawing provided will meet SPD on wheelchair housing. It would be good if they could market this as an accessible unit. We would expect the lift to be trimmed out on this plot.
- 7.9 Plots 8 and 9 accessible WC now complies and the retail access level is now provided.
- 7.10 Landscape Officer: No objection.
- 7.11 **Natural England:** Offer standing advice.
- 7.12 <u>Veolia:</u> Site is within an area defined as a Ground Water Protection Zone and require informative regarding construction work to be undertaken in accordance with British Standards. As work could exacerbate pollution.
- 7.13 **Education:** The development would generate a need for a contribution towards early years, childcare and primary level for £57,625.
- 7.14 <u>Thames Water:</u> Developer to gain consent regarding surface water drainage prior to connection to public sewers.

- 7.15 <u>Highways:</u> No objection subject to the following conditions regarding preventing surface water discharging onto highway, vehicle parking to be provided prior to occupation, construction traffic, travel information and marketing scheme and informative regarding the works.
- 7.16 <u>Drainage:</u> A sustainable drainage scheme is proposed for this site but no details have been provided therefore a condition requiring details together with a condition investigating if exceedence flows if the storage provided is exceeded.
- 7.17 Architectural Liaison Officer: Essex Police do not object but would seek a planning condition to secure by design certification is a requirement on all units. SBD approved developments are proven to create opportunities for crime. Application fails to address SBD a condition could address this. Applicants have secured certification on other sites and therefore there is no reason why this can not be achieved on this site.
- 7.18 A footpath would increase footfall through the development and increase the possibility of crime and anti/social behaviour.
- 7.19 Academic research has proven that developments like this layout with a "leaky culde-sac are most at risk to crime. Whereby cul-de sac that have no footpath access through them are low on crime. The possibility of anti-social behaviour or crime on units 9 and 10 would be high. I would oppose any public footpath.
- 7.20 Environment Agency: No objections subject to conditions relating to contamination, remediation, no infiltration of surface water drainage, if contamination not previously identified is not found and informative relating to surface water drainage, foul water disposal, water efficiency, energy ad resource efficiency and waste management.
- 7.21 Environmental Health: A site management plan is required. The geoenvironmental report submitted indicates that contamination potentially harmful to human health is present on the site therefore a contamination condition is required. Also a condition requiring demolition and construction work shall be carried out in accordance with the Uttlesford Code of Development Practice.
- 7.22 <u>Climate Change Officer:</u> Conditions relating to Code Level 3 and 10 % energy efficiency to be applied should planning permission be granted.

8. PARISH/TOWN COUNCIL COMMENTS

- 8.1 Objection for the following reasons:
 - Loss of commercial site in the village -would be well suited to a mixed use
 with starter business units which could be funded by small number of
 dwellings.
 - Recent survey by UDC shows need for 2 and 3 bed homes
 - Object to gated communities
 - No provision of pedestrian link from Cambridge Road to Crafton Green Car Park which should be a requirement of any development.
 - Highway concerns traffic backing up onto Cambridge Road Delivery vehicles etc
 which are unable to access the site would have to reverse out onto Cambridge Road
 danger to pedestrians and other road users. Vehicle exiting the site would have poor
 sight lines to the north are there are regular large lorries parked and delivering to

Tesco and the Co-op.

Further comments following re-consultation on amendments;

- Members object very strongly to application;
- Made it very clear that there should be a footpath link through to Crafton Green Car Park which it is essential, benefits to the community;
- · Do not support gated developments;
- Unconvinced that there is not a need for employment;
- Mixed use development would be acceptable
- Site visit by Planning Committee Members should be carried out.

9. REPRESENTATIONS

9.1 The neighbouring properties have been notified of the planning application and the application has been advertised on site. To date 22 representations have been received. Notification period expired 18 April 2012 further to amended plans

The responses have been received raise the following points;

- There are several businesses running on site (Your Furnished (2 outlets), Express Picture Frame, Lan One Computers, Viao Cups and the empty retail outlet occupied by Sandwich/Deli Company. The proposed demolition of all buildings to provide 1 new retail units creates a sizable shortfall in commercial premises:
- The plans are not in keeping with the High Street retail area offer;
- Removing much needed jobs and opportunities for employment. These small businesses employ a significant number of people both directly and indirectly should not be overlooked;
- The development has no visitor parking therefore would cause on street parking made worse;

The gate would make traffic worse;

- Scheme could be improved by increasing the amount of commercial outlets reducing the number of residential;
- Loss of employment would have an impact on other local businesses and local economy;
- Dangerous as delivery vehicles park close to that entrance;
- Residential would increase congestion and traffic along Cambridge Road
- Access is unsafe:
- site has always been used for commercial;
- Inappropriate to change use to residential;
- Housing is built all around at the expense of commercial;
- This part of Cambridge Road is dangerous and congested therefore no consideration should be given to schemes that would add to this problem.
- Access should be from Chapel Hill Grafton Green car park and through site for pedestrians to encourage local employment and economy;
- Need a new health centre to serve the growing population and this should be located here closer to other services;
- No link from car park to Cambridge Road through the estate. This should be required before granting any consent;
- Worried about vehicular access across a busy pavement;
- Development is in the middle of a commercial shopping zone and not comparable to area;
- Loss of site would compromise access to shopping amenities:
- Do we want to stunt amenities in one of the fastest growing area by allowing few dwellings;
- Flats should be provided above shops and offices;

- Retail provides jobs not housing developments;
- Housing density is too high and out of keeping with area;
- Retail commercial units are needed in area;
- Unsympathetic buildings will spoil area;
- Too many employment sites are being lost;
- The community would need to be long term sustainable;
- More employment sites will be left untouched to seek change of use;
- Existing on street parking and delivery hazards;
- Pedestrian safety;
- No more residential is needed:
- on street parking;
- Insufficient parking provision
- Traffic pressure on the main road could resolved through a pedestrian path being created from the public car park;
- Pressure on health services:
- Highways are not objection without a risk assessment being undertaken;
- Application would be an improvement to the site;
- Relocating from site as an occupant to other premises to allow expansion;
- There have been problems with the access being blocked;
- Concerned that development would result on a loss of sunlight and privacy due to eight of proposed dwellings. The largest house plot 4 would be located to rear of dwelling;
- Smaller two storey dwelling would be acceptable;
- Amendments does not resolve concerns by swapping Plot 4 for Plot 6
- More 2 and 3 bed affordable homes are needed within the Village

9.2 Councillor Alan Dean:

The site is in the core of the commercial and retail centre of Stansted. It should not be allowed to convert to residential, as it would have detrimental effect on the vitality of retail and other local businesses and the immediate locality. Suggested that developers were encourage to meet 5 year land supply this would be bad planning. And the Council should be planning for economic recovery and regenerating Stansted.

- 9.3 A master pan is needed linking Cambridge road with Crafton Green Car Park to relieve traffic.
- 9.4 Uncertainty regarding the medical centre proposed at Lower Street this site should be considered as an alternative. Application should be refused as road access is unsafe.
- 9.5 Amendments to scheme amendments are small in detail and do not affect earlier objections to the principle of change of use.
- 9.6 Marketing Assessment states that the PCT rejected the site for the health centre as the site access from Cambridge road was unsuitable. Existing buildings were offered not site clearance the link to Crafton Green car park would improve the prospect of the health centre.
- 9.7 The report identifies other vacant sites in the area. This does not justify the change of use of the site but the need for regeneration of the site.
- 9.8 A master plan is needed. Loss of the site to residential would undermine commercial regeneration compromising village jobs. Application should be refused.

10. APPRAISAL

- 10.1 The issues to consider in the determination of the application are:
- (A) Principle of development, demolition and the justification relating to the loss off employment site (Local Plan Policy S1, RS Policy SS1);
- (B) Scale, layout, design, amenity and sustainable construction issues (Local Plan Policies GEN2, GEN4, H10, ENV12, ENV15 & SPD: Energy Efficiency and Renewable Energy);
- (C) Highways, Accessibility and Parking (Local Plan Policies GEN1, ENV13 GEN8, RS1):
- (D) Contaminated land issues (Local Plan Policy ENV14);
- (E) Flood risk issues (Local Plan Policy GEN3.);
- (F) Impact on biodiversity (Local Plan Policy GEN7, RSS Policies ENV1 and ENV3);
- (G) Other material considerations:
- (A) Principle of development, demolition and the justification relating to the loss of employment site
- 10.2 The key message in the NPPF is that development which is sustainable should be approved without delay.and that planning should proactively drive and support economic development to deliver the homes, businesses and industrial units, infrastructure and thriving local places that the country needs.
- 10.3 Paragraph 50 of the NPPF says that in order to deliver a wide choice of high quality homes, widen opportunity for home ownership and create sustainable, inclusive and mixed communities local authorities shouldplan for a mix of housing based on current and future demographic trends, market trends and the needs of different groups in the community (such as, but not limited to, families with children, older people, people with disabilities, service families and people wishing to build their own homes).
- 10.4 The Strategic Policies and Development Management Policies forming part of the LDF are not far enough advanced to be given any weight in relation to this application.
- 10.5 The Stansted Mountfitchet Community Plan was produced by the parish council, following extensive consultation with residents, in 2011. The district council has adopted the plan as approved guidance for determining planning applications.
- 10.6 In the plan the future aspirations for the village are set out below. This site is specifically mentioned as one where the Parish Council agrees it could be provide a development opportunity for housing as the site is identified in the District Council's Strategic Housing Land Availability Assessment as a site which is suitable, available and achievable for housing. The Parish Council's response to the SHLAA was actually dependent on the site not being needed for business use.
- 10.7 Local Plan Policy S1 (within development limits in existing main urban areas) applies to areas such as Stansted Mountfitchet. It states that major urban extensions would be permitted if in accordance with the local plan and development within the existing built up areas, if compatible with the character of the settlement and in addition for sites on the edge of the built up area, its countryside setting.

- 10.8 The Council's Planning Policy section outlined that in order for this application to be acceptable the Council has to be satisfied that:
 - there is no demand for this site for business use or
 - · that the use proposed will generate local jobs
- 10.9 The site's lawful use is for the purposes of employment; however the site itself is not an identified safeguarded site due to the size of the site being less that 1.0 hectare. Local Plan Policy E2 relating to safeguarding employment land states that for site that are not key employment sites, such as the subject application site, development will be permitted of those sites where the employment use has been abandoned or the present use harms the character and amenities of the surrounding area.
- 10.10 The site is within the Development Limit of Stansted on previously developed land where in principle development is acceptable, subject to compliance with other polices of the Local Plan. With regards to the loss of employment the application site is not completely abandoned, however the level of site usage has reduced over the years and is working to below its lawful operational levels both in terms of number of staff, intensity and vehicle movements.
- 10.11 The current employment situation onsite is;

You're furnished - 3 employees. The business will be relocated to another owned site at Old Mead Road Else ham:

Lan One is a subtenant and sole proprietor. They are relocating to the immediate area;

Expensive Design is a subtenant and is relocating to the immediate area.

- 10.12 In total there are 5 employees using existing buildings.
- 10.13 All of these businesses are being and proposed to be located elsewhere around Stansted and Elsenham, and are therefore not being completely lost from the local economy in this respect. There will not be a total loss of commercial use from the site as the application seeks the redevelopment and provision of a two-storey retail unit with office over which will contribute towards the local economy and maintaining the main roads retail frontage and service provision. This is accordance with Local Plan Policies S1, E2, SM1, RS1 and RS2, RS Policies SS1, E1 and E2 also the NPPF. It is envisaged that the new retail/office unit will create a similar number of jobs to the number currently employed on site.
- A Site Marketing Assessment Report has been submitted as part of the application, which provides a detailed report as to the marketing of the site since 2008. This highlights that since the departure of the auction company from the application site many of the buildings on site have suffered from the lack of maintenance and at present the site detracts from the town centre of Stansted. It is also stated that none of the buildings have any amenity value being of a corrugated roof finish and in need of repair. It is stated that a schedule of the physical condition of the buildings have been recorded. It is stated that there is a clause within each of the leases that states "that nothing in this lease....shall require the tenant to put...the premises in any better state of repair and condition as evidenced by the Schedule of Condition annexed hereto". Further to that any improvements undertaken are at the sole expense of the tenant and would be disregarded at the time of rent

reviews.

- 10.15 This has resulted in none of the buildings being physically improved and has deteriorating since 1996 as no money has been spent on the fabric. It has been mentioned that the old showroom and main sales room is structurally unsound and the building moves in the wind. The structures are stated to be constructed of single skin concrete blocks work set in a concrete frame, where there are cracks and the walls have moved from the frames. There has been water penetration in places that in turn this has resulted in deterioration of the outer skin.
- 10.16 The situation on the main road has changed following the introduction of Tesco which has resulted in an increase in parking, traffic, and delivery servicing issues which has resulted in congestion around the sites entrance.
- 10.17 In terms of marketing the application site has been informal marketed since 2008 and officially marketed since 2010. The site was offered to a number of developers and including Co-op, Tesco and the West Essex Primary Health Trust having exposure for both the residential and commercial market.
- 10.18 The report highlights the number of other commercial units within a 15 mile radius centered on Stansted. This outlined that there are 705 buildings/ units/ suites available in this area. This breaks down to 492 Class B1 (Office business use), 138 Class B2/B8 (industrial/warehousing) and 75 units within retail (Class A1-A5). Out of this the number of mixed commercial units available within Stansted at the time of submitting the application was 20 units. Beyond the village approximately 3,000sqm of office accommodation and 2,000 sqm of B1, B2 and B8 units around the airport and Bishop's Stortford. It has been stated that 70% of the above floor space has been available for more than 24 months.
- 10.19 There is a demand to meet the Council's housing provision and this site has been considered within the District Council's Strategic Housing Land Availability Assessment (SHLAA). It has been stated within the applications submission regarding the Local Planning Authorities duty to have a 5 year land supply and that there is currently not that supply of delivery sites that needs to be provided (Section 6.12 of the Planning Statement).
- 10.20 Reference has been made to Planning Policy Statement 3 relating to Housing, however this has since been revoked after the submission of the planning application and the NPPF has precedence. Nonetheless, the newly adopted NPPF still supports the provision and delivery of new homes with a presumption in favour of sustainable development.
- 10.21 From the justification submitted as part of the application is has been demonstrated that the site has been actively marketed, that there is a saturation of other commercial units on the market, that there is no demand and that the site is in a suitable location in terms of constraints, also the existing building are beyond economic repair. In consideration of the above it is concluded that there is no demand for this site for business use and the proposed use will continue to generate local jobs through the redevelopment of the frontage. The development therefore accords with Local Plan Policies S1, E2 and SM1, also this is in accordance with the Stansted Mountfitchet Community Plan.
- 10.22 Policy H3 states that like in Policies S1 and S3 development would be permitted if compatible with its surroundings and it meets the following criteria, inter-alia;

- a) The site comprises previously developed land;
- b) Accessible;
- c) Existing infrastructure has capacity to cope with proposed development;
- d) Development would support local services and facilities;
- e) Site is not a key employment site and
- f) Avoiding development which makes inefficient use of land
- 10.23 Due to the sites locality and the nature and scale of the proposed development the scheme accords with Local Plan Policy H3.
- 10.24 Policy H4 for backland development states that "development of a parcel of land that does not have road frontage will be permitted, **if all** the following criteria are met:
 - a) There is a significant under-use of land and development;
 - b) There would be no material over looking or overshadowing of nearby properties;
 - c) Development would not have an overbearing effect on neighbouring properties; also
 - d) Access would not cause disturbance to nearby properties.
- 10.25 In terms of the amenity aspect this will be discussed below. With regards as to whether the scheme would be compatible with the character of the settlement area and countryside, the scheme would replace unsightly underused buildings within Development Limits of the Village, hence the scheme is considered to comply with Local Plan Policy H4 (a), (c) and (d).
- 10.26 The principle of demolition it has been discussed within the application. The demolition of the current building is stated would be undertaken to minimise the impact that would occur to the residential occupiers protecting their residential amenity by minimising dust and noise as part of the process. It has been emphasised that the applicants are happy for a condition to be impose requesting a methodology statement to be submitted for approval should planning permission be granted, in accordance with Local Plan Policies GEN2 and GEN4. This aspect would be a requirement should planning permission be granted, however Environmental Health would also be monitoring this aspect under their separate legislation.

(B) Scale, layout, design, amenity and sustainable construction issues

10.27 With regards to the proposed design of the scheme the NPPF, RSS Policy ENV7, also Local Plan Policy GEN2 seek for quality design, ensuring that development is compatible in scale, form, layout, appearance and materials. The policies aim to protect and enhance the quality, character and amenity value of the countryside and urban areas as a whole seeking high quality design.

Policy ENV2 Development Affecting Listed Buildings seeks for development that preserves and/or enhances their character, setting and appearance.

10.28 Overlooking:

The proposed dwellings have been sited respecting the required back to back distances. These would be of at least 25m from exiting residential dwellings located to the north (fronting Clarence Road) and east (fronting Greenfields) to the rear elevations of the proposed units, as outlined within the Essex Design Guide. Properties that consist of velux windows to the rear elevations are sited at an internal level to prevent direct overlooking. The dormer windows, which are

proposed namely on Plots 4, 5, 7, 8, 9 and 13, face inwards of the site to prevent a dominating, obtrusive appearance and overlooking. With regards to the relationship of the residential dwellings fronting Cambridge Road to the subject scheme, Plots 1-4, are side-on preventing overlooking and mitigating the impact upon outlook. Any proposed flank windows would be subject to an obscure glazing condition should planning permission be granted. This accords with local, regional and national policy.

10.29 Amenity Space:

In respect of the provision of amenity garden space the Essex Design Guide seeks 100 square metres of garden space per unit. The proposed development would provide units varying from 60-143sqm. Whilst a couple of the units would fall short of the requirement, the provision of garden space is considered to be useable and reasonable, within a town centre location while ensuring back to back distances, therefore it is considered to be acceptable.

10.30 <u>Design, Size and Scale:</u>

There is a variety of size, scale and designs surrounding the proposal.

The proposed heights of the units would vary from 8m to 10.4m and the office retail space being 7m;

- Retail/office 7m
- 8m (Plot 1, 10 and 11)
- 8.3m (Plot 2 and 3)
- 10.4m (Plot 4 and 5)
- 8.2m (Plot 6 and 14)
- 9.2m (Plot7)
- 10-10.2m (8 and 9)
- 8.4m (Plot 12)
- 9m (Plot 13)
- 10.31 Due to the distances and relationship with surrounding properties the proposed heights are considered to be generally acceptable subject to a condition relating to levels should planning permission be granted.
- 10.32 With regards to the design of the scheme it would not directly relate to a specific property as this would be difficult due to the nature of the plot. The houses general designs are standard in nature and would not be dissimilar to other properties within the District. This is acceptable and considered to accord with Local Plan Policy GEN2.
- 10.33 There is a proposed timber 5 bar gate at 1.2m in height. There would be 7m set back from the highway to the proposed access gates. Whilst there have been objections regarding a 'gated community' and it is not typically an accepted practice, there are parking issues along Cambridge Road. The proposed gates would prevent any unauthorised parking and restrict the level of movement from the existing access, reducing the risk to highway safety in accordance with Local Plan Policy GEN1 relating to Access. The proposed design of the gate would be discreet and maintain a rural appearance in keeping with its surroundings.
- 10.34 The request for an access footpath from the Crafton Green Car Park is discussed below under Section 10.52.

10.35 Impact on Listed Buildings:

Due to the orientation of the proposed dwellings in relation to the listed buildings, located on Cambridge Road, the proposed development is orient away and can not be read in relation to the Listed Buildings. No impact is considered upon the setting of the listed buildings in accordance with Local Plan Policy ENV2.

10.36 Amenity Impact on Proposed Residential Units;

A report has been undertaken by Pellings on behalf of Bellway Homes regarding the impact of the existing commercial buildings upon the proposed residential Plots 1 and 2. The report states that the proposed development is of a typical infill scheme which is surrounded by both commercial and residential properties. It specifies that the proposed internal layout of the dwellings and the relationship with the adjoining commercial retail units fronting Cambridge Road. It is highlighted that the flank wall of Tesco is rendered at the base with an eaves height of 5m with no windows in the elevation. To the rear of number 22 there is a single storey flat roof commercial building which is 3.5m high. There is a narrow gable pitched roof flank which abutts Plot 2. It is stated that due to the sun path there would be no overshadowing during the morning but some in the afternoon in the rear garden and rear elevation of Plot 1. Plot 2 is adequately set back from the shared boundary with number 22 Cambridge Road. It was concluded that the buildings fronting Cambridge Road would not have an adverse impact upon the residential amenity of proposed future.

10.37 Housing Mix:

Local Plan Policy H10 seeks that residential schemes provide a mixture of house sizes. It has been outlined within the Stansted Community Plan that there is a need for 2 and 3 bedroom units. The proposed development would provide be 6×3 bedroom units, 4×4 bedroom units and 4×5 bedroom units. This would provide a balance in the size of the family size units including meeting the need for 3 bedroom units, in accordance with Local Plan Policy H10 and the Community Plan.

10.38 Retail Unit:

The proposed retail unit has been designed to provide both retail space in order to increase and retain retail/office frontage, in accordance with Policies RS1, RS2, and E2.

10.39 The design of the proposed retail/office unit fronting Cambridge Road has been designed to be sympathetic with the surrounding heights and design of the adjacent units. The design is considered to be proportionate and in keeping with its surroundings. These accords with Local Plan Policy GEN2, RSS Policy ENV7 and NPPF.

10.40 Energy Efficiency:

Local Plan Policies GEN1 and ENV15 relating to renewable energy and the Council's Supplementary Planning Document "Energy Efficiency and Renewable Energy", RS Policies ENV1, ENV7 and ENG1 inline with NPPF seeks for sustainable development both in terms of reducing carbon footprint, promoting the use of renewable energy and locating development within accessible locations that can be served by other means of transport.

10.41 Uttlesford has a requirement for new non domestic buildings to comply with BREEAM 'Very Good' rating and for new dwellings to comply with Code Level 3, in line with national and regional policy. A report submitted with the application demonstrates how the proposed new buildings could comply with this requirement. It is confirmed within this report that this would be achieved through the use of solar

thermal panels for the residential units and air source heat pumps for the commercial units.

The Council's Climate Change Officer has raised no objection subject to the imposition of conditions should planning permission be granted relating to Code Level 3 and 10% energy efficiency. As there has been a recent change in Building Regulations residential developments achieving Code Level 3 and 10% energy efficiency can now be met through Part L of the Building Regulations therefore there is no longer a need to impose such a condition should planning permission being granted. However, the proposed development new retail unit with office space above is still required to achieve BREEAM 'Very Good', which can be ensured through a condition should planning permission be granted. Also it is illustrated within submitted drawing the provision of solar panel (drawing number 2011-147-002). This complies with Policies GEN2, and ENV15 of the local plan, also RS Policies ENV1, ENV7 and ENG1 and the Council's Supplementary Planning Document "Energy Efficiency and Renewable Energy".

(C) Highways, Accessibility and Parking

- 10.43 Local plan policy GEN1 states "development will only be permitted if it meets all of the following criteria;
 - a) Access to the main road network must be capable of carrying the traffic generated by the development safely.
 - b) The traffic generated by the development must be capable of being accommodated on the surrounding transport network.
 - c) The design of the site must not compromise road safety and must take account of the needs of cyclists, pedestrians, public transport users, horse riders and people whose mobility is impaired.
 - d) It must be designed to meet the needs of people with disabilities if it is development to which the general public expect to have access.
 - e) The development encourages movement by means other than driving a car."
- 10.44 Local Plan Policy GEN1 seeks sustainable modes of transport which is reflected within National Planning Policy Framework. This is also reflected within regional Policies SS1, T1, T2, T13 and ENV1 of the RS.
- 10.45 It is stated within the Transport Statement that the proposed development would result in a decrease in of 238 two way traffic by vehicle trips and by 99 two way operational goods vehicle trips. The above being the lawful number of vehicles that were going/capable of going in and out of the site based on its lawful use as an employment based site. Considering this together with the sites sustainable locality to the road network, bus stops and railway station the scheme is considered to be an improvement to how the site could operate if it continued in employment use. This is considered to be particularly the case considering the evolved high road concerns surrounding on-street parking and servicing of the two food stores. The proposed scheme would reduce the current risk and potential highway safety concern if the site continues to operate for employment purposes.

10.46 *Parking:*

ULP Policy GEN8 requires the parking provision to be in accordance with current adopted standards.

10.47 ECC Parking Standards September 2009 -2 spaces per dwelling (minimum) and 1 space per 30sqm for Class B1 and 1 space per 20 sqm for Class A1 (maximum). This equates to the requirement of 28 car parking spaces for the residential properties and 6 spaces for the proposed commercial units.

10.48 The proposed scheme proposes to provide 2 car parking spaces per dwelling, which include garages and 2 car parking spaces for the commercial units. The car parking provision for the dwellings and the commercial units comply with the car parking standards include the proposed sizes of the garages. Whilst the proposed parking provided for the commercial element would provide more car parking space for this particular unit than what currently exists. For example the existing retail unit fronting Cambridge Road could be separated without the need for planning permission and no on-site provision of car parking. Also, as previously stated the application site is located within an accessible area that by other modes of transport. No objection has been raised the Highway Authority regarding the proposed development subject to conditions should planning permission be granted.

10.49 Accessibility:

ULP Policy RS1 requires all retail developments to ensure that they are accessible to all in order to ensure social inclusion. It has been stated within the application submission that the scheme would be DDA compliant and accord with Part M of the Building Regulations. This is in accordance with sections (c) and (d) of Local Plan Policy GEN1.

- 10.50 Similarly the proposed dwellings will be to 'Lifetime Homes' standards with Plot 6 being specified as designated wheelchair housing. This accords with Local Plan Policy GEN1, GEN2 and SPD Accessible Homes and Play space and the golden thread of sustainability engrained within the NPPF.
- 10.51 In terms of accessibility the application site is located within/adjacent to the town centre. Immediately on Cambridge Road exiting the site there is a bus stop which would be provide good accessibility.
- Numerous request and objections have been made regarding no provision of a pedestrian footpath linking the adjacent public car park and the application site in order to get through flow onto Cambridge Road. Whilst this was a request from some residents including the Parish Council the provision of a pedestrian footpath is unacceptable in terms of introduction would increase footfall through the development and increase the possibility of crime and anti/social behaviour. The Architectural Liaison Officer stated that "...Academic research has proven that developments like this layout with a 'leaky cul-de-sac' are most at risk to crime. Whereby cul-de sac that have no footpath access through them are low on crime. The possibility of anti-social behaviour or crime on units 9 and 10 would be high." The Architectural Liaison Officer confirmed that he would oppose any public footpath through the application site. The lack of pedestrian footpath provision results in the proposed scheme complying with Local Plan Policy GEN2 (d) by helping to reduce the potential for crime.

(D) Contaminated land issues

10.53 The contamination report that has been submitted as part of the application submission concluded that there is evidence of localised ground contamination. It is stated that there were historical tanker storage on site for fuel in the garages whist they have been removed it is likely that this area would be required to be remediated to the northwest corner of the site. Should planning permission be granted a condition would be required to be imposed addressing this aspect, in accordance with Local Plan Policies ENV14 and GEN2, RS Policy ENV7 and the NPPF.

(E) Flood risk issues

- 10.54 The application site is located within Flood Zone 1 where by having a low probability of flooding. Local plan Policy GEN3, RS Policy WAT4 the protection and prevention from flooding. A flood risk assessment has been submitted as part of the application.
- 10.55 As the application site is 0.42 hectares and being located within a Flood Risk Zone one it would need to be assessed as part of any application Flood Risk submission sustainable means for surface water management.
- 10.56 It's Flood Risk Zone 1 classification means the site has low probability of flooding from tidal and fluvial sources therefore site would be pass a sequential test of any development and would not require an Exception Test that was required under the previous PPS25. The desk study also demonstrated that the site has low probability of flooding from pluvial or groundwater sources. The current site consists of 67% of permeability, whereby as part of the proposed development this figure will reduce to 8% of the total site. The application submission states that surface water attenuation would be achieved through some surface water attenuation permeable paving and some storage within the infiltration blanket.
- 10.57 It has been confirmed that there would be sufficient capacity to accommodate the foul discharge form the site. Overall the proposed development would not significantly increase the risk of flooding or increase the risk to others.
- 10.58 The Council's Drainage Engineer raised no object to the application subject to a condition being imposed relating to the seeking detail on sustainable drainage scheme together with a condition investigating exceedence flows if the storage provided is exceeded. This would accord with Local Plan Policies GEN3 and GEN2, also RS Policies WAT4 and ENV7, and the NPPF.

(F) Impact on biodiversity

10.59 Wildlife

Local plan policy GEN7 for nature conservation seeks that development that would have harmful effects upon wildlife or geological features will not be permitted unless the need for development outweighs the harm. If also seeks that a conservation survey be sought for sites that are likely to be ecologically sensitive with associated mitigation measures. Policies ENV1 and ENV3 of the RSS seeks maximising biodiversity, proper considering being given to the effects upon conservation of habitats.

10.60 In addition to biodiversity and protected species being a material planning consideration, there are statutory duties imposed on local planning authorities. Section 40(1) of the Natural Environment and Rural Communities Act 2006 states "Every public authority must, in exercising its functions, have regard, so far as is consistent with the proper exercise of those functions, to the purpose of conserving biodiversity". This includes local authorities carrying out their consideration of planning applications. Similar requirements are set out in Regulation 3(4) of the Conservation (Natural Habitats &c) Regulations 1994, Section 74 of the Countryside and Rights of Way Act 2000 and Regulation 9(5) of the Conservation of Habitats and Species Regulations 2010. Recent case law has established that local planning authorities have a requirement to consider whether the development proposals would be likely to offend Article 12(1), by say causing the disturbance of a species with which that Article is concerned, it must consider the likelihood of a licence being granted.

10.61 The tests for granting a licence are required to apply the 3 tests set out in Regulation 53 of the Habitats Regulations 2010. These tests are:

The consented operation must be for "preserving public health or public safety or other imperative reasons of overriding public interest including those of a social or economic nature and beneficial consequences of primary importance for the environment": and

There must be "no satisfactory alternative"; and

The action authorised "will not be detrimental to the maintenance of the population of the species concerned at a favourable conservation status in their natural range".

- 10.62 An Extended Phase 1 Habitat Survey has been submitted as part of the application. The buildings on site are not considered to be suitable buildings for the roosting of bats and poor opportunities for foraging habitats for bats. This is considered the case as the buildings on site consist of shallow corrugated asbestos roofs.
- 10.63 Swifts were noticed nearby and considered to be nesting on buildings close to the site. There are no trees within the site however there are several mature trees adjacent to the shared boundary with neighbouring properties namely along the west and north boundary.
- 10.64 The site appears effectively clear from items and opportunities that can provide habitats for reptile, amphibians, invertebrates and nesting birds.
- 10.65 The survey concluded there the site has low ecological value and lacks of suitable habitats therefore no further surveys are recommended. However, it has been recommended as part of the outcomes that the proposed development should include soft native landscaping and nest boxes to be included within the scheme.

The proposed development is not considered to detrimentally impact upon protected wildlife and the resultant scheme could improve the opportunities for encouraging wildlife. This accords with Local Plan Policy GEN7, Policies ENV1 and ENV3 of the RSS and the NPPF's regarding sustainability of developments.

10.66 Landscaping

As party of the application a plan has been submitted proposing measures to protect adjacent trees whilst the proposed works are on going, what is proposed to be cut back and indicative landscape proposal. Due to the lack of landscaping features on site no objection has been raised by the Council's Landscape Officer. The scheme is therefore considered to accord with Local Plan Policies GEN7 and GEN2, subject to conditions being imposed relating to protective fencing and details of landscaping should planning permission be granted.

(G) Other material consideration

- 10.67 Another material change since the granting of planning permission is the adoption of National Planning Policy Framework (March 2012). Amongst other things, this seeks a presumption in favour of sustainable development unless material considerations indicate otherwise. Also development proposals that accord with the development plan without delay. It goes onto seek high quality design and good standard of amenity for all existing and future occupants of land and buildings, promoting viability of urban areas, promoting use of brownfield land. The proposed development accords with the National Planning Policy Framework
- 10.68 The development would generate a need for a contribution towards early years, childcare and primary level and the Essex County Council Educational Services have

requested a contribution of £57,625. This has been addressed through a proposed Unilateral Undertaking.

11. CONCLUSIONS:

- 11.1 It is has been demonstrated that the site has been actively marketed, that there is a saturation of other commercial units on the market, that there is no demand and that the site is in a suitable location in terms of constraints, also the existing building are beyond economic repair. In consideration of the above it is concluded that there is no demand for this site for business use and the proposed use will continue to generate local jobs through the redevelopment of the frontage. The development therefore accords with Local Plan Policies S1, E2 and SM1, also this is in accordance with the Stansted Mountfitchet Community Plan.
- 11.2 The principle of demolition is considered to be acceptable subject to mitigation conditions should planning permission be granted.
- 11.3 The proposed design of the scheme is acceptable and in keeping subject to conditions should planning permission be granted. The setting of the existing adjacent listed buildings would be preserved. No detrimental impact is considered upon the residential or visual amenities of the existing neighbouring residential occupiers. This is in accordance with Local Plan Policies GEN2 and GEN4, The Essex Design Guide and RS Policies SS1 and ENV7.
- An Energy Efficiency report submitted with the application demonstrates how the proposed new dwellings would meet Code Level 3 and the proposed commercial unit would be achieving BREEAM 'Very Good'. It is confirmed within this report that this would be achieved through the use of solar thermal panels for the residential units and air source heat pumps for the commercial units. This accords with Policies GEN2, and ENV15 of the Local Plan, RS Policies ENV1, ENV7 and ENG1, also the Council's Supplementary Planning Document "Energy Efficiency and Renewable Energy.
- 11.5 The proposed development would result in a decrease in of 238 two way traffic by vehicle trips and by 99 two way operational goods vehicle trips. The above being the lawful number of vehicles that were going/capable of going in and out of the site based on its lawful use as an employment based site. Together with the sites sustainable locality to the road network, bus stops and railway station the scheme is considered to be an improvement to how the site could operate if it continued in employment use. The proposed scheme would reduce the current risk and potential highway safety concern if the site continues to operate for employment purposes. This accords with Local Plan Policy GEN1, Policies SS1, T1, T2, T13 and ENV1 of the RS and the NPPF.
- 11.6 The proposed car parking provision is acceptable and accords with Local Plan Policy GEN8 and the Essex Parking Standards (2009).
- 11.7 No objection has been raised by the Highway Authority, subject to conditions.
- 11.8 The proposed development would be DDA compliant, designed to Lifetime Homes standards, and there would be a designated wheelchair accessible unit. This accords with Local Plan Policy GEN1, GEN2 and SPD Accessible Homes and Play space.
- 11.9 The unacceptability of a public footpath on crime prevention grounds has been discussed in Section 10.52 above, the scheme accords with Local Plan Policy GEN2

- by helping to reduce the potential for crime.
- 11.10 Due to historical uses on site there is likely to be contamination. Should planning permission be granted a condition would be required to be imposed addressing this aspect, in accordance with Local Plan Policies ENV14 and GEN2, RS Policy ENV7 and the NPPF, also comments received from the Environment Agency.
- 11.11 There would be sufficient capacity to accommodate the foul discharge form the site. Overall the proposed development would not significantly increase the risk of flooding or increase the risk to others. Subject to a condition relating to drainage details this aspect of the scheme is considered to be acceptable and would accord with Local Plan Policies GEN3 and GEN2, also RS Policies WAT4 and ENV7, and the NPPF.
- 11.12 The proposed development is not considered to detrimentally impact upon protected wildlife and the resultant scheme could improve the opportunities for encouraging wildlife. This accords with Local Plan Policy GEN7, Policies ENV1 and ENV3 of the RSS and the NPPF's regarding sustainability of developments.
- 11.13 The lack of landscaping features on site has raised no objection from the Council's Landscape Officer. The scheme is therefore considered to accord with Local Plan Policies GEN7 and GEN2, subject to conditions being imposed relating to protective fencing and details of landscaping should planning permission be granted.

RECOMMENDATION – CONDITIONAL APPROVAL and subject to a Unilateral Undertaking regarding the provision of Education monies towards the provision of early child care and primary care for a sum of £57,625 is proposed.

- 1. The development hereby permitted shall be begun before the expiration of 3 years from the date of this decision.
 - REASON: To comply with the requirements of Section 91 of the Town and Country Planning Act 1990 as amended by Section 51 of the Planning and Compulsory Purchase Act 2004.
- 2. The development hereby permitted shall be carried out in accordance with the approved plans as set out in the Schedule.
 - REASON: For the avoidance of doubt as to the nature of the development hereby permitted, to ensure development is carried out in accordance with the approved application details, to ensure that the development is carried out with the minimum harm to the local environment, in accordance with the Policies of the Uttlesford Local Plan (adopted 2005) as shown in the Schedule of Policies.
- 3. Prior to the erection of the development hereby approved (not including footings and foundations and demolition) samples of the materials to be used in the construction of the external surfaces of the development hereby permitted shall been submitted to and approved in writing by the local planning authority. Development shall be carried out in accordance with the approved details.
 - REASON: In the interests of the appearance of the development in accordance with Policy GEN2 of the Uttlesford Local Plan (adopted 2005).
- 4. No development shall take place (excluding demolition) until full details of both hard

and soft landscape works have been submitted to and approved in writing by the local planning authority. Subsequently, these works shall be carried out as approved. The landscaping details to be submitted shall include:-

- a) proposed finished levels [earthworks to be carried out]
- b) means of enclosure
- c) car parking layout
- d) vehicle and pedestrian access and circulation areas
- e) hard surfacing, other hard landscape features and materials
- f) existing trees, hedges or other soft features to be retained
- g) planting plans, including specifications of species, sizes, planting centres, number and percentage mix
- h) details of planting or features to be provided to enhance the value of the development for biodiversity and wildlife
- i) details of siting and timing of all construction activities to avoid harm to all nature conservation features
- j) location of service runs
- k) management and maintenance details

REASON: The landscaping of this site is required in order to protect and enhance the existing visual character of the area and to reduce the visual and environmental impacts of the development hereby permitted, In accordance with Policies GEN2, GEN3, GEN4, GEN7 and GEN 8 of the Uttlesford Local Plan (adopted 2005)

5. All hard and soft landscape works shall be carried out in accordance with the approved details. All planting seeding or turfing and soil preparation comprised in the above details of landscaping shall be carried out in the first planting and seeding seasons following the occupation of the buildings, the completion of the development, or in agreed phases whichever is the sooner, and any plants which within a period of five years from the completion of the development die, are removed or become seriously damaged or diseased shall be replaced in the next planting season with others of similar size and species, unless the local planning authority gives written consent to any variation. All landscape works shall be carried out in accordance with the guidance contained in British Standards, unless otherwise agreed in writing by the local planning authority.

REASON: to ensure proper implementation of the agreed landscape details in the interest of the amenity value of the development, in accordance with Polices GEN2 and GEN7 of the Uttlesford Local Plan (adopted 2005).

6. The Retail/Office unit hereby permitted as designed, specified and built shall achieve the equivalent of a BREEAM 'very good' rating, namely the building emissions rate (BER) achieved shall be at least 25% lower than the target emissions rate (TER) as calculated by the Building Regulations 2006 Part L2A SBEM methodology, and will

incorporate other water saving and environmental features agreed with the planning authority.

The applicant will provide the planning authority with a design SBEM rating of the proposed development carried out by an accredited assessor before work commences on-site, as well as details of water saving and other environmental features. Within four weeks following its completion, the applicant will provide a SBEM rating of the as-built building and details of water saving and other environmental features incorporated.

REASON: In the interests of the promotion of sustainable forms of development and construction and construction to meet the requirements contained in adopted SPD Energy Efficiency and Renewable Energy Adopted October 2007.

7. No development (excluding demolition) shall take place until proposed levels including cross-sections of the site and adjoining land, including details of existing levels around the building(s) hereby permitted and any changes in level proposed, together with the proposed floor levels within the building(s), have been submitted to and approved by the local planning authority in writing. The development shall be carried out in accordance with the approved details.

REASON: To protect the amenities of neighbours and in order to minimise the visual impact of the development in the street scene., in accordance with Policies GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005).

8. If at any time during the course of construction of the development hereby approved, a species of animal or plant (which include bats and great crested newt) that is protected under the Conservation (Natural Habitats &c Regulations 1994) is discovered, all construction or other site work shall cease until a licence to disturb any protected species has been granted by Natural England.

REASON: To comply with the requirements of the Habitats Regulations and to protect species of conservation concern.

Protected species' are those species of plants and animals that are afforded legal protection, for example under the European Union Birds Directive and Habitats Directive (these "European Protected Species" are the highest priority for protection), or under Schedules 1, 5 and 8 of the Wildlife & Countryside Act 1981 (as amended), and the Protection of Badgers Act 1992. Developments which compromise the protection afforded European Protected Species will almost invariably require a licence from Natural England . This applies to Bats (all species) Great Crested Newt, Otter, and Dormouse.

9. The building(s) hereby approved shall not be occupied until the roads and footpaths associated with the building(s) have been constructed to base course_and surfaced in accordance with details which have been submitted to and agreed in writing by the local planning authority prior to the commencement of the development.

REASON: In order to ensure that adequate vehicular and pedestrian access is provided in the interests of highway safety, in accordance with Policies GEN1, GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005).

10. Before the commencement of the development (excluding demolition) hereby approved, details of the location and design of the refuse bin and recycling materials storage areas and collection points shall be submitted to and approved by the local planning authority. This should include provision for the storage of three standard

sized wheeled bins for each new property with a collection point no further than 25 metres from the public highway. Where the refuse collection vehicle is required to go onto any road that road shall be constructed to take a load of 26 tonnes. The refuse storage and collection facilities and vehicular access where required shall be provided prior to the first occupation of the units to which they relate and shall be retained in the approved form thereafter.

REASON: To meet the District Council requirements for recycling, to prevent the unsightly storage of refuse containers and in the interests of amenity and sustainability, in accordance with Policies GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005).

11. No development (except for demolition) shall commence until vehicular parking for site operatives (including provision for delivery and storage of materials) clear of the highway has been provided within the application site in accordance with details to be submitted to and approved in writing by the local planning authority prior to the commencement of the development, and such provision shall be retained and kept available for this purpose during construction of the development.

REASON: In order to prevent indiscriminate parking in the interests of highway safety and residential amenity, in accordance with Policies GEN1, GEN2 and GEN8 of the Uttlesford Local Plan (adopted 2005).

12. The area set aside for car parking shall be laid out and surfaced, in accordance with a scheme which has been submitted to and agreed in writing by the local planning authority before the buildings hereby permitted are first occupied and shall be retained permanently thereafter for the vehicle parking of residents/occupiers and shall not be used for any other purpose.

REASON: To ensure a satisfactory standard of development in the interests of highway safety, in accordance with Policies GEN1, GEN2 and GEN8 of the Uttlesford Local Plan (adopted 2005).

13. No development (including demolition) shall commence until wheel cleaning apparatus has been provided within the application site in accordance with details to be submitted to and approved in writing by the local planning authority prior to the commencement of the development, and which shall be operated and maintained as approved during construction of the development hereby approved.

REASON: In order to ensure that the wheels of the vehicles are cleaned before leaving the site in the interests of highway safety, in accordance with Policies GEN1 and GEN2 of the Uttlesford Local Plan (adopted 2005).

14. The first six metres of any private access way as measured from the proposed highway boundary, shall be treated with a bound surface dressing to be submitted to and approved in writing by the local planning authority before commencement of development and thereafter implemented in accordance with those approved details and retained in that form.

REASON: To prevent the tracking out of materials onto the highway in the interests of highway safety, in accordance with Policies GEN1 and GEN2 of the Uttlesford Local Plan (adopted 2005).

15. Before the commencement of the development (excluding demolition) hereby permitted, an accessibility statement/drawing shall be submitted to and approved in

writing by the local planning authority. The details submitted shall set out measures to ensure that the buildings are accessible to all sectors of the community. The dwellings shall be designed as 'Lifetime Homes' and with one Plot to be designed to be capable of being adapted for wheelchair use. All the measures that are approved shall be incorporated in the development before occupation.

REASON: To ensure that the district's housing stock is accessible to all and to meet the requirements contained in adopted SPD Accessible Homes and Playspace Adopted November 2005.

16. Before development_commences (excluding demolition) details of any proposed external lighting scheme and security measures to reduce the potential for crime have been submitted to and approved by the Local Planning Authority.

REASON: To protect the amenities of the locality by avoiding light pollution and reducing the potential for crime related activity in accordance with Policy GEN2 of the Uttlesford Local plan (adopted 2005).

17. Before development commences details of a Waste Management Plan (including the management of demolition waste) shall be submitted to and approved by the Local Planning Authority and thereafter implement in acco9rdance with the approved details.

REASON: To protect the amenities of the locality and surrounding residential occupiers preventing pollution, in accordance with Policy GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005).

- 18. No development hereby permitted shall be occupied until surface water drainage works have been implemented in accordance with details that have been submitted to and approved in writing by the local planning authority. Before these details are submitted an assessment shall be carried out of the potential for disposing of surface water by means of a sustainable drainage system in accordance with the principles set out in the former Annex F of PPS25 (or any subsequent version), and the results of the assessment provided to the local planning authority. Where a sustainable drainage scheme is to be provided, the submitted details shall:
 - Provide information about the design storm period and intensity, the method employed to delay and control the surface water discharge from the site and the measures taken to prevent pollution of the receiving groundwater and/o surface waters;
 - ii. Include a timetable for its implementation; and
 - iii. Provide a management and maintenance plan for the lifetime of the development which shall include the arrangements to secure the operation of the scheme throughout its lifetime.

REASON: To control the risk of flooding to the development and adjoining land in accordance with Policy GEN3 of the Uttlesford Local Plan (adopted 2005) and NPPF.

19. No development (excluding demolition) shall take place until details of the implementation, adoption, maintenance and management of the sustainable drainage system, incorporating details investigating exceedence flows if the storage provided is exceeded shall be submitted to and approved in writing by the local planning authority. The system shall be implemented and thereafter managed and maintained in accordance with the approved details. Those details shall include a timetable for its implementation, and a management and maintenance plan for the lifetime of the development which shall include the arrangements for adoption by any public body or

statutory undertaker, or any other arrangements to secure the effective operation of the sustainable drainage system throughout its lifetime.

REASON: To ensure suitable drainage for the development in accordance with Policies GEN2 and GEN3 of the Uttlesford Local Plan (adopted 2005).

20. The development hereby permitted shall be implemented in accordance with the ecological scheme of mitigation/enhancement submitted with the application in all respects and any variation thereto shall be agreed in writing by the local planning authority before such change is made.

REASON: In the interest of the protection of the wildlife value of the site in accordance with Policy GEN7 of the Uttlesford Local Plan (adopted 2005) and NPPF.

21. If the development hereby approved is not commenced within one year of the date of this consent a further wildlife survey of the site shall be carried out to update the information on the species and the impact of development and the survey, together with an amended mitigation strategy as appropriate, shall be submitted to and be approved in writing by the local planning authority and implemented as agreed.

REASON: To comply with the requirements of the Habitats Regulations and to protect species of conservation concern in accordance with Policy GEN7 of the Uttlesford Local Plan (adopted 2005) and NPPF.

22. Before the commencement of development a scheme for the protection of noise sensitive properties, including noise limits during construction/demolition works shall be submitted to and agreed by the Local Planning Authority, and thereafter implemented in accordance with the approved details.

REASON: In order to safeguard and protect the amenity of neighbouring residential occupiers and the locality, in accordance with Policies GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005).

23. Before the commencement of demolition a detail plan of work for demolition, also detailing measures to control noise and dust shall be submitted to and agreed by the local planning authority.

REASON: In order to safeguard and protect the amenity of neighbouring residential occupiers and the locality, in accordance with Policies GEN2 and GEN4 of the Uttlesford Local Plan (adopted 2005)

24. Demolition or construction works (including unloading of deliveries) shall not take place outside 7.30 hours to 18.00 hours Mondays to Fridays and 7.30 hours to 13.00 hours on Saturdays and at no time on Sundays or Bank Holidays.

REASON: In the interests of the amenity of the area in accordance with Policies GEN2 and GEN4 of the Uttlesford Local plan (adopted 2005).

25. Before the first occupation of the Plots 8 and 9 hereby permitted the windows(s) at first floor flank elevational shall be fitted with obscured glazing. The window(s) shall be permanently retained in that condition thereafter.

REASON: In the interests of the amenity of surrounding residential uses in accordance with Policy GEN2 of the Uttlesford Local Plan (adopted 2009) Essex

Design Guide (2005) and the SPD Home Extensions.

- 26. Prior to the commencement of development approved by this planning permission (or such other date or stage in development as may be agreed in writing with the Local Planning Authority), the following components of a scheme to deal with the risks associated with contamination of the site shall each be submitted to and approved, in writing, by the local planning authority:
 - 1) A preliminary risk assessment which has identified:
 - all previous uses
 - potential contaminants associated with those uses
 - a conceptual model of the site indicating sources, pathways and receptors
 - potentially unacceptable risks arising from contamination at the site.
 - 2) A site investigation scheme, based on (1) to provide information for a detailed assessment of the risk to all receptors that may be affected, including those off site.
 - 3) The results of the site investigation and detailed risk assessment referred to in (2) and, based on these, an options appraisal and remediation strategy giving full details of the remediation measures required and how they are to be undertaken.
 - 4) A verification plan providing details of the data that will be collected in order to demonstrate that the works set out in the remediation strategy in (3) are complete and identifying any requirements for longer-term monitoring of pollutant linkages, maintenance and arrangements for contingency action.

Any changes to these components require the express consent of the local planning authority. The scheme shall be implemented as approved.

REASON: To protect controlled waters (Secondary A Glacial sands/gravels, Secondary A Thanet Sands and Principal Aquifer Chalk), in accordance with Policies ENV12 and ENV14 of the Uttlesford Local Plan (adopted 2005).

27. Prior to commencement of development, a verification report demonstrating completion of the works set out in the approved remediation strategy and the effectiveness of the remediation shall be submitted to and approved, in writing, by the local planning authority. The report shall include results of sampling and monitoring carried out in accordance with the approved verification plan to demonstrate that the site remediation criteria have been met. It shall also include any plan (a "long-term monitoring and maintenance plan") for longer-term monitoring of pollutant linkages, maintenance and arrangements for contingency action, as identified in the verification plan, and for the reporting of this to the local planning authority. The long-term monitoring and maintenance plan shall be implemented as approved.

REASON: The potential pollution from 500 gallons underground tank and 1000 gallon above ground tank may have caused pollution soil and controlled water which may require remediation of the contamination, in accordance with Policies ENV12 and ENV14 of the Uttlesford Local Plan (adopted 2005).

28. No infiltration of surface water drainage into the ground is permitted other than with the express written consent of the Local Planning Authority, which may be given for those parts of the site where it has been demonstrated that there is no resultant unacceptable risk to controlled waters. The development shall be carried out in accordance with the approval details.

REASON: The site is located in Source Protection Zone 1 of our groundwater protection policy, in accordance with Policies ENV12 and ENV14 of the Uttlesford Local Plan (adopted 2005).

29. If, during development, contamination not previously identified is found to be present at the site then no further development (unless otherwise agreed in writing with the Local Planning Authority) shall be carried out until the developer has submitted, and obtained written approval from the Local Planning Authority for, a remediation strategy detailing how this unsuspected contamination shall be dealt with. The remediation strategy shall be implemented as approved.

REASON: Heterogeneity of hydrogeology and historic use contamination not identified in site investigation may be present, in accordance with Policies ENV12 and ENV14 of the Uttlesford Local Plan (adopted 2005).


30. Notwithstanding the provisions of the Town and Country Planning (General Use Class) Order 1995 (or any Order revoking or re-enacting that Order with or without modification), the hereby permitted retail unit and Office unit shall remain in use Classes A1 and B1 (a) purposes only and shall not change use class without the prior written permission of the local planning authority.

REASON: To prevent the loss of employment and in order to safeguard the retails frontage in accordance with Policies GEN2, GEN4, E1, E2 and SM1 of the Uttlesford Local Plan (adopted 2005).

Background papers: see application file.

UTT/2473/11/FUL





Reproduced from the Ordnance Survey mapping with the permission of the Controller of Her Majesty's Stationery Office.

Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings.

Uttlesford District Council Licence No: 100018688 (2007).

DATE16/05/2012

MAP REFERENCE: TL4926 NW

SCALE:1:1250